SCHEDULE Article 3

## The Scheduled Works

In the borough of Gosport in the county of Hampshire-

## Work No. 1 The construction of two temporary causeways comprising stone and geotextile fabric having a height of one metre and a width of 9 metres at the base and a width of 5 metres at the uppermost part thereof—

- (A) one commencing on the south side of Forton Lake at reference point SU461705100867 and extending in a northerly direction for a distance of 60 metres and terminating in Forton Lake at reference point SU461707100924; and
- (B) the other commencing on the north side of Forton Lake at reference point SU461709101014 and extending in a southerly direction for a distance of 75 metres and terminating in Forton Lake at reference point SU461709100939.
- Work No. 2 A bridge over Forton Lake constructed with reinforced concrete, supported on bored reinforced concrete piles and having an opening span over the navigable channel affording a height upwards without limit above the level of high water and a clear width over that channel of not less than 11 metres, commencing on the south side of Forton Lake at reference point SU461706100840 and extending in a northerly direction for a distance of 202 metres and terminating on the north side of Forton Lake at reference point SU461705101042.
- Work No. 3A A series of mooring piles to be placed in Forton Lake, to the west of the bridge, to enable vessels to moor temporarily, prior to navigating through the bridge, commencing at reference point SU46166100916, extending in an easterly direction for a distance of 15 metres and terminating at reference point SU461681100918.
- Work No. 3B A series of mooring piles to be placed in Forton Lake, to the east of the bridge to enable vessels to moor temporarily prior to navigating through the bridge, commencing at reference point SU461737100940, extending in an easterly direction for a distance of 15 metres and terminating at reference point SU461752100942.