SCHEDULE 1

PART 4

MEASURES TO BE TAKEN IN RESPECT OF DANGEROUS SUBSTANCES

- 3. The responsible person must—
 - (a) ensure that the premises are designed, constructed and maintained so as to reduce risk;
 - (b) ensure that suitable special, technical and organisational measures are designed, constructed, assembled, installed, provided and used so as to reduce risk;
 - (c) ensure that special, technical and organisational measures are maintained in an efficient state, in efficient working order and in good repair;
 - (d) ensure that equipment and protective systems meet the following requirements—
 - (i) where power failure can give rise to the spread of additional risk, equipment and protective systems must be able to be maintained in a safe state of operation independently of the rest of the plant in the event of power failure;
 - (ii) means for manual override must be possible, operated by employees competent to do so, for shutting down equipment and protective systems incorporated within automatic processes which deviate from the intended operating conditions, provided that the provision or use of such means does not compromise safety;
 - (iii) on operation of emergency shutdown, accumulated energy must be dissipated as quickly and as safely as possible or isolated so that it no longer constitutes a hazard; and
 - (iv) necessary measures must be taken to prevent confusion between connecting devices;
 - (e) where the work is carried out in hazardous places or involves hazardous activities, ensure that appropriate systems of work are applied including
 - (i) the issuing of written instructions for the carrying out of work; and
 - (ii) a system of permits to work, with such permits being issued by a person with responsibility for this function prior to the commencement of the work concerned.