Status: This is the original version (as it was originally made). This item of legislation is currently only available in its original format.

SCHEDULE 1

Authorised project

PART 2

Temporary jetty works

In the District of West Somerset and the County of Somerset and the territorial sea

Work No. TJ1

A jetty of open piled construction including an elevated roadway and comprising a concrete deck supported on steel tubular piles, commencing at a point at ST1953846080 and extending in a north westerly direction into Bridgwater Bay for a distance of 506 metres and terminating at a point at ST1928546519, the location of which is shown on sheet no. 7 and the sections of which are shown on sheet no. 10.

Work No. TJ2

A covered conveyor for transporting aggregates to be used on Work Nos. 1A, 1B and 1C, commencing at a point at ST1968845829 and extending in a north westerly direction for a distance of 788 metres and terminating at a point at ST1931146515, the location of which is shown on sheet no. 8 and the sections of which are shown on sheet no. 10.

Work No. TJ3

A pipeline for transporting cement and cement replacement products to be used on Work Nos. 1A, 1B and 1C, commencing at a point at ST1968846053 and extending generally in a north westerly direction for a distance of 655 metres and terminating at a point at ST1929246510, the location of which is shown on sheet no. 9 and the sections of which are shown on sheet no. 10.

Work No. TJ0

Demolition and removal of Work Nos. TJ1, TJ2 and TJ3 shown on sheet nos. 7, 8 and 9 and associated restoration work.